

	WORKS	DESCRIPTION	UNITS	MATERIAL+EQUIPMENT	LABOR	TIME	DAILY OUTPUT	TOAL COST + OVERHEAD + %10 PROFIT	SOURCE
2 site earthwork	foundation	strip footing, backfill and all form included	linear foot						R.S. Means
		2.6 KLF, 3 KSF soil, 16"x8" deep		5.45	10.9			16.35	
		3.9 KLF, 3 KSF soil, 24"x8" deep		6.95	12.05			19	
		5.1 KLF, 3 KSF soil, 24"x12" deep		11.25	18.15			29.4	
		11.1KLF, 6 KSF soil, 24"x12" deep		11.25	18.15			29.4	
		6.8KLF, 3 KSF soil, 32"x12" deep		13.95	19.85			33.8	
		14.8 KLF, 6 KSF soil, 32"x12" deep		13.95	19.85			33.8	
		9.3 KLF, 3 KSF soil, 40"x12" deep		16.65	21.5			38.15	
		18.4 KLF, 6 KSF soil, 40"x12" deep		16.8	22			38.8	
		spread footing, excavation backfill and all form included	each						R.S. Means
		25K, 3 KSF soil, 3' sq, 12" deep		46.5	93			139.5	
		50K, 3 KSF soil, 4'6" sq, 12" deep		99	161			260	
		50K, 6 KSF soil, 3' sq, 12" deep		46.5	93			139.5	
		75K, 3 KSF soil, 5'6" sq, 13" deep		157	227			384	
		75K, 6 KSF soil, 4' sq, 12" deep		80.5	138			218.5	
		100K, 3 KSF soil, 6' sq, 14" deep		199	273			472	
		100K, 6 KSF soil, 4'6" sq, 15" deep		122	189			311	
		slab on grade, non industrial	square foot						R.S. Means
		4" reinforced/non reinforced		1.56/1.44	2.32/2.03		3.98/3.47		
		5" reinforced/non reinforced		1.93/1.71	2.37/2.08		4.30/3.79		
		6" reinforced/non reinforced		2.41/2.07	2.43/2.04		4.84/4.11		
		7" reinforced/non reinforced		2.78/2.35	2.52/2.11		5.3/4.46		
		8" reinforced/non reinforced		2.98/2.62	2.49/2.14		5.47/4.76		