

Adobe Brick, Semi-stabilized, with cement mortar

	Daily Output	Labor-hours	Unit (S.F.)	Material	Labor & Equipment	
10x4x14"	560	0.071	2.6	2.9		2.55
12x4x16"	580	0.069	2.3	4.45		2.46
10x4x16"	590	0.068	2.3	4.23		2.42
8x4x16"	560	0.071	2.3	3.07		2.55
4x4x16"	540	0.074	2.3	2.53		2.65
6x4x16"	540	0.074	2.3	2.55		2.65
4x4x12"	520	0.077	3	2.28		2.75
8x4x12"	520	0.077	3	2.51		2.75

Total	Total (O&P)
5.45	7.05
6.91	8.65
6.65	8.35
5.62	7.25
5.18	6.8
5.2	6.85
5.03	6.7
5.26	6.95