

STUCCO	Crew	Daily Output	Labor Hours
3 coats 1" thick, float finish, with mesh, on wood frame	J-2	63	0.762
On Masonry construction, no mesh incl.	J-1	67	0.597
For trowel finish, add	1 PLAS	170	0.047
For 3/4" thick, on masonry, deduct	J-1	880	0.045
For coloring and special finish, add, minimum	J-1	685	0.058
Maximum	J-1	200	0.2
Soffits, add	J-2	155	0.31
Ext stucco, w/bonding agent, 3 coats, on walls, no mesh	J-1	200	0.2
Ceilings	J-1	180	0.222
Beams	J-1	80	0.5
Columns	J-1	100	0.4
Mesh, painted, nailed to wood, 1.8 lb.	1 LATH	60	0.133
3.6 lb.	1 LATH	55	0.145
Wired to steel, painted, 1.8 lb.	1 LATH	53	0.151
3.6 lb.	1 LATH	50	0.16

Unit	Material	Labor	Equipment	Total	Total (O&P)
S.Y.	5.5	25.5	1.92	32.92	46.5
S.Y.	2.15	19.95	1.81	23.91	34.5
S.Y.	0	1.65	0	1.65	2.5
S.Y.	0.6	1.52	0.14	2.26	3.11
S.Y.	0.39	1.95	0.18	2.52	3.58
S.Y.	1.35	6.7	0.61	8.66	12.3
S.Y.	2.09	10.4	0.78	13.27	18.9
S.Y.	3.5	6.7	0.61	10.81	14.65
S.Y.	3.5	7.4	0.67	11.57	15.85
S.Y.	3.5	16.7	1.52	21.72	31
S.Y.	3.5	13.35	1.21	18.06	25.5
S.Y.	4.8	4.64	0	9.44	12.2
S.Y.	3.37	5.05	0	8.42	11.2
S.Y.	4.8	5.25	0	10.05	13.1
S.Y.	3.37	5.55	0	8.92	11.95